



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Plugging Authority issued
Jan 17, 1975

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sun Oil Company 1-28-75
 Complete Address 1720 S. Bellaire, Suite 300, Denver, Colo-80222
 Lease Name Gus Miller "A" Well No. #3
 Location C. SW. NW. Sec. 7 Twp. 22 Rge. (E) (W) 22
 County Hodgeman Total Depth 4621
 Abandoned Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated _____
 Plugging Contractor Charlie Crow Drilling
 Address Hays Kans. License No. 733
 Operation Completed: Hour 12:30 PM Day 27th Month Jan Year 1975

The above well was plugged as follows:

Surface casing set 265 ft 8/8 with 200 sacks
 Cement Circulated. Perforations from 4542 -
 4540. 4620 ft of 5 1/2" plugged 4525 with sand
 3 sacks of Cement. First plug set at 850 ft
 2 sacks of Hulls then 50 sacks of cement. 10
 sacks of premium fell to 550 ft. Then 35 sacks
 of cement. 10 sacks of premium fell to 40 ft.
 10 sacks of cement from 40-0 ft. This was

I hereby certify that the above well was plugged as herein stated.

Accomplished by Sun
 Cementing of Hays, Kans.
 2497 ft 5 1/2" casing salvage.

Signed: Clarence J. Thomas
 Well Plugging Supervisor

INVOICED

DATE 1/30/75

INV NO 731-w