



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1975

CONSERVATION DIVISION
Wichita, Kansas

1-28-75

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

*Plugging Authority issued
Jan 17, 1975.*

Operator's Full Name Sun Oil Company

Complete Address 1720 S. Bellair, Suite 300, Denver Colo.

Lease Name Gus Miller "A" Well No. #4

Location C. 5.W. N.E. Sec. 7 Twp. 22 Rge. (E) (W) 22

County Hodgeman Total Depth 4655

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Charke Bros Drilling

Address Hays, Kansas License No. 733

Operation Completed: Hour 10:30 AM Day 27th Month Jan Year 1975

The above well was plugged as follows:

*There was 264 ft of 8 1/8" circulated with 200
sacks of cement. There was 4652 ft of 5 1/2" casing.
Perforations were from 4563-4568. Sand to
4550 filled with 3 sacks cement. 1 ft plug set
at 850 ft with 50 sacks cement. Filled with
premium Jell 10 sacks to 550 ft. 10 premium Jell
to 40 ft. Then 10 sacks cement from 40-0.*

This was accomplished by sun cementing of

I hereby certify that the above well was plugged as herein stated.

*Hays, Kans
There was 2764 ft 5 1/2"
casing salvaged.*

Signed Lawrence J. Thomas
Well Plugging Supervisor

DATE 1/30/75

INV. NO. 732-W