

KANSAS

2 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address Box 308, Great Bend, Kansas

Lease Name Hann "C" Well No. 3

Location C SE NW Sec. 27 Twp. 22 Rge. 22 (EX) (W)

County Hadgeman Total Depth 4431'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Southwest Casing Pulling

Address Great Bend, Kansas License No. 399

Operation Completed: Hour 3:00Pm Day 15 Month 1 Year 1971

The above well was plugged as follows:

8 5/8" to 286' circulated w/ cement. 5 1/2" to 4429' cemented.

Open Hole From 4429' to 4431' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4300' Mud 4300' to 500'

Spotted 150 sacks cement 500' to 0'. Hallibutton Pump Truck.

Pulled 2815' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Lewis
Well Plugging Supervisor

INVOICED

DATE 1/18/71
INV. NO. 3225-4