

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address 705 4th Nat'l Bk., Bldg., Wichita, Kansas 67202

Lease Name Ruff "B" Well No. 1

Location 150' NW C SW NE Sec. 25 Twp. 22 Rge. 22(E) (W)

County Hodgeman Total Depth 4530'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Russ Casing Pulling

Address Great Bend, Kansas License No. 623

Operation Completed: Hour 2:00PM Day 11 Month 9 Year 1971

The above well was plugged as follows:

8 5/8" to 277' circulated w/ cement. 5 1/2" to 4527' cemented.

No perforation- 3' Open hole. Plug bottom w/ sand & 5 sacks cement.

Top of cement 4460' Mud 4460' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 270'

Spotted 30 sacks cement 270' to 170' Mud 170' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Globe Cementing Pump Truck.

Pulled 2920' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:   
Well Plugging Supervisor

DATE 9-22-71

INV. NO. 4350-W