

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP. 14 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Co.

Complete Address 705 4th Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Ruff "A" Well No. 1

Location C SE NW Sec. 25 Twp. 22 Rge. 22 (~~EE~~) (W)

County Hodgeman Total Depth 4515'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Russ Casing Pulling Co.

Address Box 1082, Great Bend, Kansas License No. 623

Operation Completed: Hour 11:00Am Day 9 Month 9 Year 1970

The above well was plugged as follows:

8 5/8" to 280' circulated w/ cement. 5 1/2" to 4506' cemented.

No perfs, open hole to 4515' Plug bottom w/sand & 5 sacks

Top of cement 4440' Mud 4440' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 280'

Spotted 30 sacks cement 280' to 180' Mud 180' to 40'

Plug, Halls & 10 sacks cement 40' to 0'. Globe Cementing Pump

Pulled 2424' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9-14-70

INV. NO. 2522-W