


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
812 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 19 Twp. 22 Rge. 13 (E) W (W)
Location as "NE/CNW&SW&W" or footage from lines NW NW NE
Lease Owner Trans Era Petroleum, Inc.
Lease Name Moses-Aldrich Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 3/26/54 19
Application for plugging filed 3/25/54 19
Application for plugging approved 3/25/54 19
Plugging commenced 3/26/54 19
Plugging completed 3/26/54 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3945 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	315'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Layed down drill pipe. Filled hole with heavy mud to 300', set first plug at 300', 1/3 sack of hulls and 20 sacks of cement were used. Filled hole with mud to 30', set second plug at 30', 1/3 sack of hulls and 10 sacks of cement were used.

RECEIVED
STATE CORPORATION COMMISSION

APR 2 1954

4-2-54

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature)

H. R. Michaelis

Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 54

Margie Cooper

Notary Public.

My commission expires 1-30-57.

PLUGGING
FILE SEC 19 T 22 R 13W
BOOK PAGE 23 LINE 30

Trans Era Petroleum, Inc.
Roses-Aldrich #1

NW NW NE 19-22-18
Stafford County, Ks.

Total Depth: 3945'
Comm. 3/11/54
Comp. 3/26/54

Casing

8 5/8" Set @ 315'

Cement

230 sacks of Lehigh

Formation	Depth
Sand-clay	15
Sand	155
Sand-clay-gravel	296
Red bed	315
Red bed-shale	785
Anhydrite	810
Shale-shells	1310
Salt-shale	1510
Shale-shells	1645
Lime-shale	3522
Lime	3582
Lime-shale	3624
Lime	3722
Lime-shale	3868
Shale	3942
Shale-lime	3945'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Cora Betz

Subscribed and sworn to before me this 1st day of April, 1954.

Margie Cooper

Notary Public

My commission expires: 1-30-57.

PLUGGING
FILE SEC 19T-22-13W
BOOK PAGE 23 LINE 30

STAFFORD COUNTY, KANSAS
NOTARY PUBLIC