


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

STAFFORD County, Sec. 19 Twp. 22S Rge. 13W (E) (W)
Location as "NE/CNW%SW%" or footage from lines CE 2-NE-SE
Lease Owner AMERICAN PETROLEUM, INC.
Lease Name MOSES Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-3-60 19
Application for plugging filed 3-2-60 19
Application for plugging approved 3-2-60 19
Plugging commenced 3-2-60 19
Plugging completed 3-3-60 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging, was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot, St. John, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled hole with heavy mud 3900' up to 300'. Set bridge using 1/3 sk. hulls, wood plug, 20 sx. cement through drill pipe. Filled hole with heavy mud up to 35'. Set bridge using 1/2 sk. hulls, wood plug, 10 sx. to cellar zero.

Job completed: 1:30 a.m. - 3-3-60.

Plugging supervisor: Mr. Frank Broadfoot
St. John, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address Box 232, Russell, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
C. I. HONAKER, Drilling Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. I. Honaker
Box 232, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1960

My commission expires 10-17-63 Notary Public.



American Petro., Inc. - Operator

Sierra Petro. Co., Inc. - Contractor

MOSES #1
CE2-NE-SE
19-22S-13W
Stafford County, Kansas

Elev.: 1910' K.B.
T.D. : 3900'

Commenced: 2-21-60
Completed: 3-3-60

Casing:

8-5/8" @ 325'

Cement:

w/ 250 sacks

FORMATION	DEPTH
Sand - Shale	270
Shale	310
Shale - Shells	500
Red Bed - Shale	780
Anhydrite	805
Shale - Sheels	1190
Shale - Salt	1370
Shale - Shells	1730
Lime - Shale	3294
Lime	3381
Lime - Shale	3518
Lime	3698
Lime - Shale	3747
Lime, Shale & Chert	3809
Cherty Viola	3823
Lime - Shale	3879
Arbuckle	3900

TOPS:	DEPTH
Anhydrite	780
Heebner	3310
Tronto	3327
Douglas	3349
Brown Lime	3441
Lans./ K.C.	3456
Viola	3792
Arbuckle	3879

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1960
CONSERVATION DIVISION
Wichita, Kansas

3310
1910
-1400

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Hensler

Subscribed and sworn to before me this 4th day of March 1960.

Geroy Dwyer
Notary Public

My commission expires: 10-17-63