

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 7 Twp. 22S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner Thunderbird Drilling, Inc.

Lease Name Perdue Well No. 1

Office Address 1311 Union Nat'l. Bank Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 24 19 56

Application for plugging filed March 24 19 56

Application for plugging approved March 24, 19 56

Plugging commenced March 24 19 56

Plugging completed March 24 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundridge

Producing formation Depth to top Bottom Total Depth of Well 3840 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	300 feet 8 5/8" Surface casing set with 210 sacks cement, Calcium Chloride			3 sacks gel, 3 sacks		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled to 240 feet with heavy mud. Plug set at 240 feet with 1/3 sack hulls. 20 sacks cement mixed and pumped through drillpipe, hole filled with mud to 35 feet. Plug set at 35 feet with 1/3 sack hulls, 10 sacks cement mixed and pumped on top of plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.

Address 1311 Union National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. J. W. Owen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Owen

1311 Union Nat'l. Bank Bldg, Wichita Kansas

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 56

Leta Helm Notary Public.

My commission expires August 25, 1956

PLUGGING
FILE SEC 7 Twp 22 R 13W
BOOK PAGE 48 LINE 21

3-29-56

THUNDERBIRD DRILLING, INC. & LEE PHILLIPS
#1 PERDUE

LOCATION: SW SW SE - Sec. 7,
Twp. 22.S, Rge 13.W.,
Stafford County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
1311 Union National Bank Building
Wichita, Kansas

SURFACE CASING: 300' 8 5/8" cemented with 210 sacks
cement, 3 sacks gel, 3 sacks
Calcium Chloride.

OIL STRING: None

ELEVATION: 1915' K. B.
1912' D. F.
1910' G. L.

COMMENCED: March 13, 1956

COMPLETED: March 24, 1956

WELL LOG

0	-	195	Surface Clay
195	-	285	Sand
285	-	300	Shale
300	-	779	Red Bed
779	-	810	Anhydrite
810	-	1650	Shale & Shells
1650	-	1725	Shale & Lime
1725	-	1910	Broken Lime
1910	-	2150	Lime
2150	-	2300	Shale & Lime
2300	-	2835	Shale & Shells
2835	-	3235	Shale & Lime
3235	-	3290	Lime
3290	-	3410	Shale & Lime
3410	-	3650	Lime
3650	-	3740	Shale & Lime
3740	-	3767	Chert
3767	-	3795	Shale & Sand
3795	-	3815	Shale
3815	-	3840	Lime
3840			Rotary Total Depth

The undersigned, J. W. Owen, an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Perdue as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

J. W. Owen

J. W. Owen, Sec.-Treas.

Subscribed and sworn to before me
this 27th day of March, 1956.

Leta Helm

Leta Helm - Notary Public

My commission expires:
August 25, 1956.

