

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,954-0000

LEASE NAME Clyde Shulz

WELL NUMBER #1

SPOT LOCATION C SE SW SE

SEC. 7 TWP. 22S RGE. 13 (W)

COUNTY Stafford

Date Well Completed 3-6-84

Plugging Commenced 3:00 PM,
3-6-84

Plugging Completed 4:45 PM,
3-6-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Walter Oil and Gas, Inc.
ADDRESS 240 Main Building - 1212 Main Street
Houston, Texas 77002

PHONE # (713) 659-1221 OPERATORS LICENSE NO. 9289

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation D & A Depth to top bottom T.D. 3861'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	307'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. 50 sacks at 3800'; 50 sacks at 780'; 40 sacks at 360'; 10 sacks, 1/2 sack hulls and Howco plug for bridge at 40'; 15 sacks in rathole. Used 60/40 Pozmix, 2% gel and 4% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Kansas 67579

MAR 16 1984
SUBSCRIBED AND SWORN TO before me this 7th day of March, 1984.

CONSERVATION DIVISION
Wichita, Kansas

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85



STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - CLYDE SHULZ #1
 Located: C SE SW SE, Section 7-22S-13W, Stafford County,
 Kansas

OWNER: Walter Oil and Gas, Inc.

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 1, 1984

COMPLETED: March 6, 1984

TOTAL DEPTH: 3861'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 280 Sand	Ran 7 joints 8 5/8", 23# casing. 295.30'
280 - 783 Shale	pipe set at 307' K.B. Cemented with 275
783 - 800 Anhydrite	sacks 60/40 Pozmix, 2% gel and 3% cc.
800 - 3861 Lime and Shale	Plug down at 5:15 PM, 3-1-84, by Howco.
	Plugged.

Deviation Surveys: 1 1/2° at 1806'
 2° at 3861'

RECEIVED
 STATE CORPORATION COMMISSION

MAR 16 1984

CONSERVATION DIVISION
 Wichita, Kansas