

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 20 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-30096-0000

LEASE NAME Staub #1

WELL NUMBER _____

SPOT LOCATION SW NW NE

SEC. 36 TWP. 22S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 3/23/84

Plugging Completed 3/30/84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graves Drilling Co., Inc.

ADDRESS 910 Union Center, Wichita, Ks. 67202

PHONE # (316) 265-7233 OPERATORS LICENSE NO. #5428

Character of Well _____
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3839'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	370'	none
				5 1/2"	3687'	2081'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Sanded to 3530' & 5 sacks cement. Shot pipe at 3019', 2917', 2815', 2712', 2610', 2507', 2405', 2301', 2197', & 2081'. Pulled 63 joints. Pumped well with 2 hulls, 10 gel, 50 cement, 1 hull, 10 gel, released plug, & 100 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
 STATE CORPORATION COMMISSION

APR 05 1984

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 1984

CONSERVATION DIVISION
 Wichita, Kansas
 My Commission Expires: _____



Irene Hoover
 Notary Public

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves, et al DRILLING COMMENCED: March 19, 1965
 412 Union Center
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: March 28, 1965
 412 Union Center
 Wichita, Kansas

CASING RECORD: 11 Jts. 370' 8-5/8" LOCATION: Staub No. 1
 cemented with 400 sacks SW NW NE
 111 Jts. 3687' 5-1/2" Section 36-22S-14W
 cemented with 125 sacks Stafford County, Kansas

0 - 349	Sand	3120 - 3170	Lime
349 - 396	Red bed	3170 - 3210	Shale & lime
396 - 828	Red bed & shale	3210 - 3311	Lime
828 - 848	Anhydrite	3311 - 3441	Lime & shale
848 - 1605	Shale & shells	3441 - 3457	Brown lime & shale
1605 - 2005	Lime & shale	3457 - 3630	Lime
2005 - 2143	Lime & shale streaks	3630 - 3743	Lime & shale
2143 - 2395	Lime & shale	3743 - 3780	Lime & chert
2395 - 2638	Shale with lime	3780 - 3830	Shale
2638 - 2802	Shale & lime streaks	3830 - 3833	Lime & shale
2802 - 3075	Shale & lime	3833 - 3839	Lime
3075 - 3120	Lime & shale	3839	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John C. Graves* President

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1965

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 7th day of April, 1965.

My commission expires:

April 30, 1967

Betty Brangt
Betty Brangt Notary Public