


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 36 Twp. 22 Rge. 14 ~~EO~~ W (W)

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Fleming & Woodman, et al
Lease Name Beaver Well No. 1
Office Address 921 Union Nat'l Bank Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 29 1954
Application for plugging filed " 1954
Application for plugging approved " 1954
Plugging commenced " 1954
Plugging completed " 1954
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with 230' heavy mud, 1 1/2 gal hulls in sack below bottom plug-cemented with 20 sacks cement, filled hole with heavy mud to within 40' of top - tied plug and cemented with 10 sacks of cement

7-10-54

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1954

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor M. A. Rives
Address Pratt, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) K. T. Woodman

921 Union National Bank Bldg, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 1954

Frances S. Webber
Notary Public.

My commission expires March 18, 1958



FLEMING & WOODMAN DRILLING COMPANY

DRILLERS WELL LOG

Fleming & Woodman, et al - #1 Beaver
 Commenced - June 18, 1954
 Completed - June 29, 1954

SW SW NW Section 36-22-14W
 Stafford County, Kansas

Depth		Formation	Remarks
From	To		
0	110	Sand	
110	230	Shale & shells	Ran 8 5/8" surface pipe at 230' Cemented with 200 sacks cement
230	280	Shale & red bed	
280	360	Sand	
360	835	Red bed	
835	868	Anhydrite	
868	1118	Red bed & shale	
1118	1520	Shale & shells	
1520	1600	Shale & sand	
1600	3255	Shale & lime	
3255	3305	Lime	
3305	3457	Shale & lime	
3457	3505	Lime	
3505	3780	Lime	Elevation 1927 R.B.
3780	3802	Viola Lime	Anhydrite (driller) 850
3802	3835	Shale & sand	Heebner 3328
3835	3854	Conglomerate	Dodge 3345
3854	3880	Arbuckle	Brown Lime 3457
			Lansing 3473
			Conglomerate 3755
			Viola 3769
			Simpson Shale 3800
			Arbuckle 3854
			Total Depth 3880

PLUGGING
 FILE SEC 36-22-14W
 BOOK PAGE 45 LINE 38

EXECUTED, this 7th day of July, 1954.

STATE COMMISSIONER

JUL 8 1954

K. T. Woodman

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS.

CONSERVATION DIVISION
 Wichita, Kansas

Before me, the undersigned, a Notary Public, within and for said county and State, on this 7th day of July, 1954, personally appeared K. T. Woodman to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that the above is a true and correct copy as set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

James L. Miller
 Notary Public

My Commission Expires March 18, 1958