


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County, Sec. 36 Twp. 22 Rge. 14 (E) (W) X
Location as "NE/CNW/SE/SW" or footage from lines NE SE NW
Lease Owner Graves Drilling Co. Inc.
Lease Name Bartlett Well No. #1
Office Address 505 Union Center Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-12-74 19
Plugging completed 2-21-74 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3826' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3824'	2012.20'
				8 5/8"	368'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3550'. Mixed and ran 5 sacks cement thru dump bailer.
Plugged hole with 2 sacks hulls - 20 sacks gel and 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION


FEB 25 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)



Subscribed and sworn to before me this 22 day of February, 1974
Sidney D. Miller
Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves, et al DRILLING COMMENCED: December 1, 1964.
412 Union Center
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: December 9, 1964
412 Union Center
Wichita, Kansas

CASING RECORD: 10 Jts. 368' 8-5/8" LOCATION: Bartlett No. 1
cemented with 325 sacks NE SE NW
106 Jts. 3824' 5-1/2" Section 36-22S-14W
cemented with 105 sacks Stafford County, Kansas

0 - 368	Sand & shale
368 - 825	Red bed, shale & sand
825 - 849	Anhydrite
849 - 1680	Shale & shells
1680 - 2090	Lime & shale
2090 - 2265	Lime
2265 - 2335	Lime with shale
2335 - 3030	Shale & lime
3030 - 3210	Lime
3210 - 3321	Lime & shale
3321 - 3439	Shale & lime streaks
3439 - 3455	Brown lime & shale
3455 - 3773	Lime
3773 - 3822	Shale & sand
3822 - 3826	Lime
3826	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1973
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves President

STATE OF KANSAS)
) SS
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 14th day of December, 1964.

My commission expires: April 30, 1967

Betty Brandt
Betty Brandt Notary Public