

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bluff Building
Wichita, Kansas

NORTH

Section Plat grid with 4 columns and 4 rows.

Locate well correctly on above
Section Plat

Harvey County, Sec 26 Twp 22 Rge 3 (E) W (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SMC SE/4 NE/4
Lease Owner Penguin Petroleum, Inc.
Lease Name Shive Well No. 1
Office Address 507 Rule Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 27, 19 54
Application for plugging filed April 27, 19 54
Application for plugging approved April 27, 19 54
Plugging commenced April 27, 19 54
Plugging completed April 27, 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 3278 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8-5/8", 177'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from 3278' to 260', plug set at 260', 25 sacks of cement from 260' to 200', plug set at 25', 5 sacks of cement from 25' to 6', surface soil from 6' to 0'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mr. J. A. Melland
Address 1111 No. Main St.
Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. G. Talbott, Pres., Penguin Pet., Inc. (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.G. Talbott
507 Rule Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of May, 19 54

My commission expires May 25, 1957

PLUGGING
FILE SEC 26 T 22 R 3W
BOOK PAGE 31 LINE 2

28-3390-s 6-51-20M

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 - 1954 5-6-1954
CONSERVATION DIVISION
Wichita, Kansas

WELL RECORD

LEASE NAME Shive WELL NO. 1 ELEVATION _____

LOCATION SWC SE/4 NE/4 Sec. 26-22S-3W, Harvey County, Kansas

WORK COMMENCED April 16, 1954 DRILLING COMMENCED April 17, 1954

DRILLING COMPLETED April 27, 1954

DRILLING CONTRACTOR J. A. Melland, 1111 North Main Street, Hutchinson, Kansas

ROTARY DRILLING FROM 0' TO 3278'

FORMATION: FROM TO REMARKS

Top soil, sand, shale & shells 0 85
Sand, shale & shells 85 177 Set and cemented 8-5/8" OD 2 1/2" casing at 177' w/ 175 sacks of cement and 2 sacks of calcium chloride. Cement circulated.

Shale and shells 177 380
Shale & lime 380 485
Lime & shale 485 525
Anhydrite 525 550
Lime & shale 550 700
Broken lime 700 880
Shale & lime 880 1135
Shale & lime 1135 1440
Shale & shells 1440 1675
Shale & lime 1675 1925
Lime & shale 1925 2080
Broken lime 2080 2275
Lime & shale 2275 2525
Shale with lime streaks 2525 2660
Lime & shale 2660 2920
Shale & lime 2920 3020
Lime & shale 3020 3120
Lime & shale 3120 3175

Cherty lime 3175 3205 Circ. for samples @ 3125' 1/2 hr.
Circ. for samples @ 3167' 3/4 hr.
Circ. for samples @ 3187' 1 hr.
Circ. for samples @ 3205' 1 hr.
Ran Schlumberger Survey 8 hrs.
Ran Halliburton D.S.T. from 3165' to 3205', open 1 hr., recovered 20' of drilling mud, 9 hrs. 21 min.

Chert & lime 3205' 3231' Circ. for samples @ 3230' 1 hr. 30 min.
Circ. at 3231' 1 hr. 48 min.
Ran Halliburton D.S.T. #2 from 3163' to 3231', open 1 hour, recovered 60' of gas cut mud, BHP-635# 9 hrs.

Lime & shale 3231' 3278' Circ. for samples @ 3249' 1 hr.
Circ. for samples @ 3278' 1 hr.
Circ. @ 3278' 1 hr. 45 min. waiting on plugging orders.

TOTAL DEPTH 3278' As no oil or gas was encountered in commercial quantities, authority was granted to plug the well under directions of Ruel Durkee, S.O.C. well plugger, as follows: Heavy mud from 3278' to 260', plug set at 260', 20 sacks of cement from 260' to 200', plug set at 25', 5 sacks of cement from 25' to 6', surface soil from 6' to 0', plugged and abandoned 4/27/54. Slope tests taken at regular intervals showed no deflections from the vertical.

AFFIDAVIT

STATE OF Kansas, COUNTY OF Renov, SS

I, J. A. Melland, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

PLUGGING
MAY SEC 26-22-3W
PAGE 31 LINE 2

Subscribed and sworn to before me this 1st day of May 1954.

J. A. Melland

Oscar A. Huber
Notary Public