

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Harvey SEC. 26 TWP. 22S RGE. 3W E/W
Location as in quarters or footage from lines:
1120' FNL 990' FEL NW/4

Lease Owner Vincent Oil Corporation
Lease Name Franz-Schrag #1 Well No. _____
Office Address 1110 Kansas State Bank Bldg. 125 N. Market Wichita,
Character of Well (Completed as Oil, Gas or Dry Hole): Ks. 67202
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4-30-82
Plugging completed 5-6-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merlan Unruh

Producing formation _____ Depth to top _____ bottom _____ T.D. 3250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	213'	None
				4-1/2"	3249'	2239'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Well had gas on it, loaded hole with salt water and pumped in 50 sacks common cement,
bottom plug @3000'. Shot casing @2751', 2636', 2520', 2404', 2326' and 2258'.
Pulled a total of 59 joints of 4-1/2" casing. Plugged well with 5 sacks hulls, 10 sacks
gel, 150 sacks 50/50 pos, 2% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 82



My Commission expires: _____

Irene Hoover
Notary Public.

RECEIVED

MAY 13 1982

5-13-82

CONSERVATION DIVISION
Wichita Kansas

15.079-20319-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- FRANZ-SCHRAG #1
Located: 1120' FNL, 990' FEL, NW/4, Section 26-22S-3W,
Harvey County, Kansas

OWNER: Vincent Oil Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 25, 1977
COMPLETED: October 2, 1977

TOTAL DEPTH: 3250'

LOG

0 - 125 Sand
125 - 693 Shale
693 - 2825 Lime and Shale
2825 - 3220 Lime
3220 - 3250 Miss.

CASING RECORD

Ran 6 joints 10 3/4" OD casing, 213' cemented
at 225' IKB with 250 sacks 60/40 Pozmix,
2% gel and 3% cc. Plug down at 2:30 PM,
9-25-77.

Ran 88 joints of 4 1/2" new and used casing,
3268.49' pipe set at 3249' K.B. Cemented
with 100 sacks 50/50 Pozmix with 18% salt
and 3/4 of 1% CFR-2 with 20 barrels salt
flush ahead of cement. Plug down at 2:00
PM, 10-2-77, by Howco.

Phone 913-493-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

15079-20319-0000

Phone Plainville 913-466-4666
 Phone Kiowa 316-825-4148

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell Kansas 67685

No. 28247

Date	Sec.	Twp.	Range	Called Out	On Location	Job Start	Finish
8-27-26	26	24	4W	8:10 AM	10:30 AM		11:00 AM
Lease	Well No.	Location			County	State	
Swing	1	Buda on 22nd SS			Harvey	K	

Contractor: <i>[Signature]</i>		Owner	
Type Job: <i>Plug of casing</i>		To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Hole Size: <i>14" - 7 1/2"</i>	T.D. <i>3250'</i>	Charge To: <i>Vincent Oil Co.</i>	
Csg. Size: <i>4 1/2" - 10 3/4"</i>	Depth: <i>27' - 27'</i>	Street: <i>110 Kansas State Bank Bldg</i>	
Trp. Size: <i>3 2 5/8" - 2 1/3"</i>	Depth: <i>27' - 27'</i>	City: <i>State</i>	
Drill Pipe:	Depth: <i>27' - 27'</i>	The above was done to satisfaction and supervision of owner agent or contractor.	
Tools:	Depth:	Purchase Order No.	
Cement Lbr in Csg.:	Shoe Joint	X	<i>Helen Casing</i>
Feet Max <i>300</i>	Minimum <i>0 - shut in</i>	CEMENT	
Mass Line:	Displace <i>45 - shut in</i>	Amount Ordered	<i>50 SXS Cem</i>

Perf. <i>50 - OVERALL</i>		EQUIPMENT <i>went on vacuum</i>		Consisting of	
No.	Cement	<i>Kevin R.</i>		Common	<i>50 SXS @ 475</i>
<i>120</i>	Helper	<i>mike O</i>		Poz. Mix	
No.	Cement			Gel.	
	Helper			Chloride	
	Driver	<i>Otis</i>		Quickset	
<i>134</i>	Driver				

DEPTH of Job		Sales Tax	
Reference:		Handling <i>50 SXS</i>	<i>.50</i>
		Mileage	
		Sub Total	
		Total	
		Floating Equipment	
		STATE OF KANSAS COMMISSIONER	

Remarks: *Filled casing to get injection rate. Never hit pressure Pump 50sxs com @ 300lbs. Went on vacuum. Pumped 40 bbls. displacement. Sent 5 more bbls on vacuum to 45 bbls. 50 bbls. OVERALL*

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

15-079-20319-0000

Phone Plainville 913-434-2912
 Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31
 Russell, Kansas 67665

No. 29734

Date	5-6-82	Sec.	26	Twp.	22	Range	3	Called Out		On Location	2:00 PM	Job Start		Finish	3:15 PM
Lease		Well No.	# 1	Location				6N 2 1/2 E BURTON				County	State		

Contractor	
Type Job	plug to abandon
Hole Size	T.D. 3250
Csg. Size	Depth
Tbg. Size	Depth
Drill Pipe	Depth
Tool	Depth
Cement Left in Csg.	Shoe Joint
Press Max. 500	Minimum
Meas. Line	Displace

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	VINCENT OIL CORP
Street	
City	State
The above was done to satisfaction and supervision of owner agent or contractor.	

Ref. 3234-37 3221-25 3169-76
EQUIPMENT

Pumptrk	No. 120	Cementer	Roger
		Helper	CURTIS
Pumptrk	No.	Cementer	
		Helper	
Bulktrk	134	Driver	BUB
Bulktrk		Driver	

Purchase Order No.	X Bill Fulls @ Kelso Casing Pulling
Amount Ordered	10 gel 150 5/50 3% CC 2% GEL
Consisting of	CEMENT 5 hulls

DEPTH of Job	pump truck	360.00
Reference:	1 10 3/4 plug #100 miles @ #100	
	Sub Total	
	Tax	
	Total	

Common	75	
Poz. Mix	75	
Gel.	13	
Chloride	5	
Quickset		
Hulls	5	
	173	Sales Tax
Handling	5X @	904
Mileage	miles @	664
		Sub Total
		Total

Remarks: mixed 5 hulls, 10 gel
 shut in @ #500

Floating Equipment

150 cement