


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Pawnee County. Sec. 34 Twp. 22 Rge. 18 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Sterling Drilling Co. et al  
Lease Name Abrahamson Well No. 1  
Office Address Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed January 4, 1956  
Application for plugging filed January 4, 1956  
Application for plugging approved January 4, 1956  
Plugging commenced January 4, 1956  
Plugging completed January 4, 1956  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage,  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4724 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy to  
bottom of surface casing.  
Set bottom plug at 320' and  
filled hole with 100 sacks  
cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company  
Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead  
Sterling, Kansas  
(Address)

Subscribed and sworn to before me this 10th day of January, 1956

My Commission Expires Jan. 22, 1958  
My commission expires \_\_\_\_\_

Bernard Landermilk  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 12 1956 1-12-56

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 34-22-18W  
BOOK PAGE 29 LINE 36

GROUP EXPLORATION COMPANY  
Sterling, Kansas

WELL LOG-----ABRAHAMSON #1

Location: NE NE SE, Section 34-22S, 18W,  
Pawnee County, Kansas

OWNER: Sterling Drilling Company, et al.  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 12-14-55 (w.r.)  
COMPLETED: 1-5-56 (w.r.)

TOTAL DEPTH: 4724'

LOG

0-300	Clay & Shale
300-440	Shale
440-540	Red Bed
540-1180	Shale
1180-1850	Shale & Shells
1850-2330	Limestone & Shale
2330-2575	Limestone
2575-3810	Shale & Limestone
3810-4170	Limestone
4170-4271	Limestone & Shale
4271-4293	Conglomerate
4293-4380	Chert
4380-4520	Limestone
4520-4565	Shale & Limestone
4565-4590	Sand & Shale
4590-4610	Simpson Sand
4610-4655	Limestone & Shale
4655-4674	Shale
4674-4724	Arbuckle Limestone T.D.

CASING RECORD

Ran 325' of 8-5/8" casing set with  
200 sacks cement, 2% calcium chloride.

PRODUCTION

Plugged & Abandoned

TO WHOM IT MAY CONCERN: This is to certify that this is a correct record of the Drillers' time sheets for the Abrahamson #1 well.

RECEIVED  
STATE GEOLOGICAL COMMISSION

JAN 12 1956

CONSERVATION DIVISION  
Wichita, Kansas

STERLING DRILLING COMPANY

By Hollin Mead  
Hollin Mead, President

Subscribed, and sworn to me this 9th day of January, 1956.

My Commission Expires Jan. 22, 1958

<b>PLUGGING</b>
FILE REC-34-22-18W
BOOK PAGE 29 LINE 36

Bernard Landersmilk  
Notary Public