

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21,160-0000

LEASE NAME Barger

WELL NUMBER 1

SPOT LOCATION C NE NE

SEC. 28 TWP. 22 RGE. 18 (W)

COUNTY Pawnee

Date Well Completed 9-11-84

Plugging Commenced 9-12-84

Plugging Completed 9-12-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation, Inc.

ADDRESS 125 N. Market - Suite 1110, Wichita, Kansas 67202

PHONE #(316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4605

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. well was plugged with 120 sxs 60/40 poz; 2% gel, 3% cc as follows: 1200'-50 sxs; 500'-40 sxs; 40'-10 sxs with plug; rathole-10 sxs; mousehole - 10 sxs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

**9-28-84
RECEIVED**

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Pratt, ss.

SFP 28 1984

Tracy C. Graven (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tracy C. Graven


(Address) _____



SUBSCRIBED AND SWORN TO before me this 27 day of September, 1984

Mary L. Tjaden
Notary Public

My Commission expires: 3/22/88



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Barger #1
 C NE NE Sec. 28-22S-18W
 Pawnee County, Kansas
 Commenced: 9-1-84
 Completed: 9-12-84
 API #15-145-21,160
 Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	120	Red Bed, Sand	Ran 12 joints (442'), new, 23#, 8 5/8" surface casing. Set at 454' with 175 sxs Lite, 3%cc, 100 sxs Common, 3% cc, 2% gel. Job by Buie. Cement did circulate. Plug down at 1:30 p.m. on September 2, 1984.
120	1297	Red Bed	
1297	2500	Shale	
2500	4605	Lime, Shale T.D.	

RTD 4605'

Well was plugged with 120 sxs 60/40 poz, 2% gel, 3% cc as follows: 1200'-50 sxs; 500'-40 sxs; 40'-10 sxs with plug; rathole 10 sxs; mousehole-10 sxs. Job by Buie, ticket #3146. Plug down at 6:30 a.m. on September 12, 1984. Plugging office was out of Dodge City, Kansas.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

RECEIVED
 STATE CORPORATION COMMISSION

Tracy C. Shaven
 TRACY C. SHAVEN

SEP 28 1984



Mary L. Tjaden
 NOTARY PUBLIC

CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires:

3/22/88