


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 27 Twp. 22 S. Rge. 18W (XXXXXX)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner Derby Oil Co. and Coppinger Drilling, Inc.

Lease Name Grant Well No. 1

Office Address 320 Union Nat'l Bank Bldg., Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-2-1954

Application for plugging filed 9-2-1954

Application for plugging approved 9-2-1954

Plugging commenced 9-2-1954

Plugging completed 9-2-1954

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 4685 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 225' of top. Pushed plug to 225'

Cemented with 20 sacks. Filled hole to 35' of top.

Pushed plug to 35' and filled with 15 sacks of cement.

9-8-54

RECEIVED  
KANSAS STATE CORPORATION COMMISSION

SEP 11 1954

CONSERVATION DIVISION

Name of Plugging Contractor Coppinger Drilling, Inc.

Wichita, Kansas

Address 320 Union National Bank Bldg., Wichita 2, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lee Poulsen

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lee Poulsen


320 Union Nat'l Bank Bldg., Wichita, Kansas.

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 1954

My commission expires March 7, 1956

Notary Public.



DRILLERS LOG

Contractors: Coppinger Drilling, Inc  
320 Union Natl Bk Bldg  
Wichita 2, Kansas

Re: Derby Oil & Coppinger  
Drilling, Inc.  
Grant #1  
SE SE NE Sec. 27-22-18W  
Pawnee County, Kansas

Surface clay	190
Sand	200
Shale	225
Red Shale	500
Red Bed	650
Sand	850
Red bed & shale	1170
Anhydrite	1195
Blue and red shale	1225
Red bed and shale	1245
Salt and shale	1280
Shale	1334
Shale and shells	2055
Chalk & lime	2070
Lime and shale	2140
Lime	2175
Lime and shale	2745
Lime	2760
Lime and shale	2790
Lime	2810
Lime and shale	3030
Shale	3075
Shale and lime	3130
Lime	3140
Lime and shale	3400
Shale	3425
Lime	3480
Lime and shale	3575
Shale	3665
Lime and shale	3718
Shale	3724
Lime	3780
Lime and chert	3815
Lime and shale	3870
Lime	3955
Lime and shale	3980
Sand	3991
Lime and chert	4005
Lime	4045
Lime and Shale	4090
Lime	4155
Lime and shale	4210
Shale	4250
Sand	4260
Shale and lime	4285
Chert	4321
Chert and lime	4332
Chert and shale	4350
Shale and lime	4415
Lime and chert	4433
Lime and shale	4465
Lime and chert	4506
Lime	4532
Lime and chert	4580
Conglomerate	4553
Simpson	4615
Shale	4637
Dolomitic limestone	4685

R T D

4685

D &amp; A

## Casing Record:

Set 8-5/8" @ 225' with 150 sac  
pozzex cement.

## Tops:

Anhydrite	1170
Heebner	3694
Brown Lime	3786
Lansing	3796
Conglomerate	4244
Mississippi	4285
Kinderhook Lime	4391
Viola	4458
Simpson	4553
Arbuckle	4637
Rotary Total Depth	4685

## D &amp; A

Commenced: August 14, 1954  
Completed: Sept. 2, 1954  
Elevation: 2089' R.E.  
2087' D.F.

State of Kansas, County of Sedgwick - ss.

I, the undersigned, being duly sworn on  
oath, state that the above statement and  
log is a true record and log of the well  
drilled at the location above described.

*Lee Paulsen*

Subscribed and sworn to before me this  
3rd day of September 1954.

*Marjorie Broedius*  
Notary Public

My commission  
expires: March 7, 1956



REIVED  
CORPORATION COMMISSION

SEP - 3 1954

CONSERVATION DIVISION  
Wichita, Kansas

