


Give All Information Completely  
Make Read Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 22 Twp. 22 Rge. 18 (E) (W)  
Location as "NE/CNW/SE" or footage from lines SW SW NE  
Lease Owner Welch & Olsson Drilling Co. Inc.  
Lease Name Vinson Well No. 1  
Office Address 203 Rule Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 8-25 19 55  
Application for plugging filed 8-25 19 55  
Application for plugging approved 8-25 19 55  
Plugging commenced 8-25 19 55  
Plugging completed 8-25 19 55  
Reason for abandonment of well or producing formation D and A  
If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Ks.  
Producing formation Depth to top Bottom Total Depth of Well 4575 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 212'   | none       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full of mud. Set wooden plug. Pumped  
and displaced with 85 sacks of cement with Service  
Truck

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.  
Address 203 Rule Bldg. Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. E. Welch (employee or owner or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.


(Signature)

203 Rule Bldg. Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of August, 19 55

My commission expires June 12, 1959

Notary Public.



RECEIVED  
STATE CORPORATION COMMISSION

SEP 1 1955  
CONSERVATION DIVISION  
Wichita, Kansas

9-6-55

WELL LOG.

WELCH &amp; OLSSON DRILLING COMPANY, INC.

ELEVATION: 2072 R.B.

CONTRACTOR: WELCH &amp; OLSSON DRILLING CO. INC.

Comm. Drlg: 8-9-55

VINSON NO. 1

Comp. Drlg: 8-25-55

SW SW NE 22-22-18W.

Pawnee County, Kansas.

Production: D &amp; A

## Casing Record.

Set 212' of 8 5/8" with 175 sacks of cement.

(Figures indicated bottom of formations.)

FORMATIONS:DEPTHSFORMATION TOPS.

|                          |           |
|--------------------------|-----------|
| Surface Clay:            | 180       |
| Shale:                   | 400       |
| Red Bed: 600             | 600       |
| Sand:                    | 690       |
| Red Bed:                 | 1105      |
| Anhydrite:               | 1125      |
| Shale & Shells:          | 1700      |
| Shale and Shells W/salt: | 1800      |
| Shale W/shell stks:      | 1930      |
| Shale & Lime:            | 2100      |
| Lime & Shale:            | 2395      |
| Lime:                    | 2490      |
| Lime & Shale:            | 2600      |
| Lime:                    | 2625      |
| Lime & Shale:            | 2660      |
| Shale & Shells:          | 2905      |
| Shale & Lime:            | 2990      |
| Shale & Shells:          | 3125      |
| Shale & Lime:            | 3318      |
| Lime:                    | 3530      |
| Lime & Shale:            | 3730      |
| Lime:                    | 4215      |
| Conglomerate:            | 4257      |
| Miss. Chert:             | 4275      |
| Shale & Lime:            | 4356      |
| Lime & Chert:            | 4380      |
| Chert:                   | 4420      |
| Lime:                    | 4448      |
| Lime-Chert:              | 4465      |
| Sand & Shale:            | 4505      |
| Lime:                    | 4513      |
| Sand:                    | 4543      |
| Shale:                   | 4553      |
| Lime:                    | 4575 T.D. |

|                      |      |         |
|----------------------|------|---------|
| Heebner:             | 3637 | (-1565) |
| Brown Lime:          | 3730 | (-1658) |
| Lansing-Kansas City: | 3740 | (-1668) |
| Conglomerate-Cherty: | 4214 | (-2142) |
| Mississippi:         | 4257 | (-2185) |
| Kinderhook:          | 4274 | (-2202) |
| Viola:               | 4340 | (-2268) |
| Simpson Sand:        | 4513 | (-2441) |
| Simpson Shale:       | 4531 | (-2459) |
| Arbuckle:            | 4553 | (-2481) |

STATE OF KANSAS,

SS:

SEDGWICK COUNTY,

**PLUGGING**
 FILE SEC 22 T 22 R 18W  
 BOOK PAGE 146 LINE 10

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SW SW NE of Section 22, Township 22, Range 18 West, Pawnee County, Kansas.

WELCH &amp; OLSSON DRILLING COMPANY, INC.

BY

R. E. WELCH

Subscribed and sworn to before me this 31st day of August, 1955.

Edith Erker, Notary Public.

 My commission expires:  
 June 12, 1959