


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 14 Twp. 22 Rge. 18 E/W  
Location as "NE/CNW/SW" or footage from lines

NW SE NE  
Lease Owner Bell Brothers  
Lease Name Eddy A#1 Well No.  
Office Address 201 N. Jefferson, Robinson, Ill 62451  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6-15-79 19  
Plugging completed 6-26-79 19  
Reason for abandonment of well or producing formation  
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin  
Producing formation Depth to top Bottom Total Depth of Well 4250  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
6/61 L 2 111	7-27-79			8-5/8	275	None
				5 1/2"	4249	1963
RECEIVED STATE CORPORATION COMMISSION						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Sanded to 4050' and ran 5 sacks cement. Had Allied pump mud down surface pipe  
rigged up and shot pipe at 2900', 2583', 2395', 2176', 2081', pulled 10 joints  
and mud came in. Had Allied pump mud, pulled 50 joints and had Allied pump  
well, pulled 5 joints and pumped 140 sacks cement down casing and surface, had  
water truck suck out cellar. Filled with 5 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING, CHASE, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.  
Jim L. Wright (employee of ~~XXXXXX~~ of ~~XXXXXX~~ operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

*Jim L. Wright*

1020 Hoover, Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 79.

*Thomas W. Sloan*

Notary Public.

My commission expires

10-26-79

15-145-20380-0000

# WELL LOG

COMPANY Bell Brothers

SEC. 14 T. 22S R. 18W

FARM A.D. Eddy A NO. 1

LOC. NW SE NE

RIG. NO. 7


TOTAL DEPTH 4250'

COUNTY Pawnee  
KANSAS

DDMM. 3-15-75

DDMM. 3-28-75

CONTRACTOR Rains & Williamson Oil Co., Inc.



### CASING

20	10		
15		8-5/8" @ 275 w/200 sx 60/40 pos, 3% CCELEVATION	2044 GL
12	6		2% gel
13		5 1/2" @ 4249 w/landing jt, w/150 SX PRODUCTION	Oil
		50/50 pos, salt saturated.	

FIGURED INDICATE BOTTOM OF FORMATIONS

Sand & Shale	275
Shale	533
Sand	635
Shale & Sand	1098
Anhydrite	1120
Shale	1495
Shale & Lime	3065
Lime & Shale	3697
Lime	3826
Lime & Shale	3894
Lime	4000
Lime & Shale	4015
Lime	4250
<u>Rotary Total Depth</u>	<u>4250</u>

RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1979

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Sedgwick ) ss:

I, Wilson Rains, President of the Rains & Williamson Oil Company, In

upon oath state that the above and foregoing is a true and correct copy of the log of the A.D. Eddy A-1 well.

Wilson Rains  
Wilson Rains

Juanita M. Green  
NOTARY PUBLIC  
Juanita M. Green.

Subscribed and sworn to before me this 31st day of March 19 75

My Commission Expires: October 4, 1975

