

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20,256-0000

LEASE NAME Strobel

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 13 TWP. 22S RGE. 18W (E) or (W)

COUNTY Pawnee

Date Well Completed

Plugging Commenced 11-2-93

Plugging Completed 11-5-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pintail Petroleum, Ltd.

ADDRESS 225 N. Market, Suite 300 Wichita, KS 67202

PHONE # (316) 263-2243 OPERATORS LICENSE NO. 5086

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	252'	none
				5 1/2	4340'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Sanded bottom @ 4060' & 5 sks cement. Shot @ 3200, 2800, 2400 & 2200. Pulled to 1260, pumped
10 sks gel. Pulled to 1225, pumped 50 sks cement, displaced it down. Pulled to 715, pumped
5 sks gel. Pulled to 700, pumped 100 sks cement & 300# hulls. Pulled to 425, circulated cement
to surface. 60/40 pos 2% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS. 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum, Ltd.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso RECEIVED

(Address) P. O. BOX 347 CHASE, KS. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of November, 19 93

Irene Herzberg
Notary Public
CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires:



11-15-93
Form CP-4
Revised 05-88

Stroke #1 SW SW NE 13-22-18

Rawson Co.

15-145-20256-0000

1	
2	OPT #
3	15-145-20-313
4	15-145-20,256
5	Surface
6	8 5/8" - 252'
7	
8	Cement 175 st
9	
10	
11	
12	Long string 140 f's 5 1/2"
13	4340'
14	
15	Cement 165 st
16	
17	
18	
19	Perforations
20	4114 - 22
21	
22	
23	
24	
25	
26	
27	
28	P.B.T.D. 4124
29	
30	

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1993

CONSERVATION DIVISION
Wichita, Kansas