

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,065-0000

LEASE NAME Veatch

WELL NUMBER 1

SPOT LOCATION C S/2 SE NW

SEC. 29TWP. 22SRGE. 13W(E) or (W)

COUNTY Stafford

Date Well Completed 8/15/84

Plugging Commenced 8/15/84

Plugging Completed 8/15/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

PHONE # (316) 682-3022 OPERATORS LICENSE NO. 8061

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #1, Dodge City, KS

Is ACO-1 filled? To be filed If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put in	Pulled out
		0'	347'	8-5/8"	340.70'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged with 50 sacks 60-40 Pozmix Cement, 2% Gel, 3% CaCl₂ at 800'; 40 sacks cement at 390'; bridge plug and 10 sacks cement at 40'; and 15 sacks cement in rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor The Buie Co., Inc. License No. _____

Address N. Highway 281, Pratt, KS 67124

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley, Agent (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the logs of the above-described well, and that the same are true and correct. So help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) [Signature]
(Address) 221 S. Broadway, Suite 400
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1984
Wichita, Kansas

My Commission expires: March 12, 1987

Notary Public

15.185.22065.0000

Oil Producers, Inc. of Kansas - Veatch #1
P.O. Box 8647 C S/2 SE NW Sec. 29-22S-13W
Wichita, Kansas 67208 Stafford County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: August 9, 1984
Completed: August 15, 1984

Drillers Log

Sand	290
Red Bed	350
Red Bed & Shale	590
Red Bed	785
Anhydrite	809
Shale	1290
Shale & Shells	1710
Shale	2645
Shale & Shells	2860
Shale & Lime	3425
Lime & Shale	3520
Lime	3890 RTD

Casing: 347' 8-5/8" cemented with 200 sacks 65-35 Pozmix Cement,
2% Gel, 3% Calcium Chloride.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1984

CONSERVATION DIVISION
Wichita, Kansas