


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 6 Twp. 22S Rge. 14 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SE NE SE
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Estes Well No. 1
Office Address Liberty Bank Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Mar. 16, 19 57
Application for plugging filed Mar. 16, 19 57
Application for plugging approved Mar. 16, 19 57
Plugging commenced Mar. 16, 19 57
Plugging completed Mar. 16, 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation Depth to top Bottom Total Depth of Well 3896 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	302'	8 5/8"	302'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 3896' to 240' - heavy rotary mud and wooden plug
240' to 132' - 35 sacks cement
132' to 40' - heavy rotary mud and wooden plug
40' to 6' - 15 sacks cement
6' to surface- cellar

3-20-57
RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY: Al H. Smith
P.O. Box 88, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of March, 19 57

Ruth Brant

My commission expires April 27, 1960

Notary Public.

PLUGGING
FILE SEC 6 T 22 R 14W
BOOK PAGE 148 LINE 36

DRILLERS' LOG

Company: Anderson-Prichard Oil Corporation SE NE SE
 Farm Name: Estes Well No. 1 Sec. 6, Twp. 22S, Rge. 14W,
 Total Depth: 3896' County: Stafford, Kansas
 Comm: 3/5/57 Comp: 3/16/57 Elevation:
 Contractor: Peel Brothers, Inc. Production: Dry
 Casing: 8 5/8" @ 302' cem.

Figures below indicate bottoms of formations:

Sand and clay	0 -	95
Clay		140
Sand		250
Shale		302
Red bed and sand		880
Anhydrite		910
Red bed		1155
Shale and sand		1690
Lime		1925
Lime and shale		2140
Lime, sand and shale		2260
Lime		2375
Lime and shale		3195
Lime		3320
Lime and shale		3415
Lime		3710
Lime and shale		3785
Lime		3792
Chert and lime		3845
Conglomerate		3880
Lime and chert		3896
Total Depth		3896

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 18th day of March, 1957

My commission expires: April 27, 1960

Ruth Brank
Notary Public

RECEIVED
STATE COMMISSION

MAR 20 1957

COMMISSION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 6 T 22 R 14W
BOOK PAGE 148 L 36