


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

## WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County, Sec. 6 Twp. 22 Rge. 14 W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C SW SW SW  
Lease Owner Petroleum, Inc.  
Lease Name SHARP C Well No. 1  
Office Address 800 R.H. Garvey Bldg, 300 West Douglas, Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 1 19 75  
Application for plugging filed December 1 19 75  
Application for plugging approved December 1 19 75  
Plugging commenced December 1 19 75  
Plugging completed December 1 19 75  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3930 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole full of heavy mud. Plug @ 500' w/40 sacks cement thru drill pipe.  
Come up hole to 270' plug w/25 sacks cement thru drill pipe.  
Top plug @ 40' w/1 sack hulls and 10 sacks cement.  
2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.  
Address Box 823, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON

Larry Curtis

(employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 823, Great Bend, Kansas 67530

(Address)

Subscribed and Sworn to before me this 2nd day of December

19 75

My commission expires April 11, 1978

Dorothy M. Wagne

Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 4 1975

12-4-1975

CONSERVATION DIVISION  
Wichita, Kansas

## DRILLERS' WELL LOG

DATE COMMENCED: November 24, 1975  
 DATE COMPLETED: December 1, 1975

Petroleum, Inc.  
 SHARP C-1  
 C SW SW 34 of Sec 6-T22-R14  
 Stafford County, Kansas

ELEVATION: 1959 K.B.

## FORMATION TOPS

0 - 194' Sand  
 194 - 279' Sand, Shale  
 279 - 350' Red Bed  
 350 - 875' Sand, Shale  
 875 - 2610' Shale and Lime  
 2610 - 3353' Lime and Shale  
 3353 - 3357' Shale  
 3357 - 3485' Lime and Shale  
 3485 - 3704' Lime  
 3704 - 3775' Lime and Shale  
 3775 - 3784' Lime, Shale, Chert, Sand  
 3784 - 3850' Chert  
 3850 - 3908' Shale  
 3908 - 3930' Dolomite  
 3930' RTD

Anhydrite	883
Heebner	3353
Brown Lime	3476
Lansing	3485
Base K.C.	3704
Cong.	3775
Viola	3784
Simpson Shale	3850
Arbuckle	3908
RTD	3930

## SURFACE PIPE:

Set 279' of new 5 5/8", 20# pipe  
 w/225 sacks 50/50 Pozmix, 2/Gel,  
 3/ cc.

## AFFIDAVIT

STATE OF KANSAS }  
 COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 3rd day of December, 1975.

Marjorie M. Lague  
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 4 1975

CONSERVATION DIVISION  
 Wichita, Kansas