


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Building Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 14 Twp. 22S Rge. 13W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner Crown Oil Company, Inc.
Lease Name Fischer Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19.
Application for plugging filed April 17, 1951 19.
Application for plugging approved April 18, 1951 19.
Plugging commenced 4-13-51 19.
Plugging completed 4-17-51 19.
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"		2881'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole to 3500' and ran 5 sacks cement.
Mudded hole to 314' and set rock bridge to
300'. Ran 15 sacks cement, mudded hole to 30'
and ran 10 sacks cement on top. Well complet-
ed.

4-24-51

RECEIVED
CORPORATION COMMISSION
APR 24 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Crown Oil Company, Inc.
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. B. Bayless (employee of owner) or (owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) M. B. Bayless
P. O. Box 164, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of April 1951

Harry Seacork
Notary Public.

My commission expires June 13, 1951

PLUGGING
FILE SEC. (4-T-24R13a)
BOOK PAGE 7 LINE 25


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GREAT LAKES CARBON CORP. & CROWN OIL
Farm - Fischer No. 1

SEC. 14 T. 22 R. 13W
SW SW NE

Total Depth. 3788'
Comm. 3-4-49 Comp. 3-24-49
Shot or Treated.
Contractor. Crown Oil Co., Inc.
Issued. 6-18-49

County. Stafford
KANSAS



CASING:
8-5/8" 314' Cem. #/300 Sx.
5-1/2" 3770'

Elevation. _____

Production. 31 bbls.

Figures Indicate Bottom of Formations.

cellar	4
sand	185
shale & sand	275
red bed	685
lime	715
red bed	940
shale & shells	1210
shale & salt	1415
salt	1550
shale & shells	1700
lime brkn	1765
lime	2145
lime & shale brks	2270
lime & shale	2455
shale & shells	2710
shale & lime	2795
shale & shells	2995
shale	3005
lime	3055
lime & shale	3130
lime	3220
lime & shale brks	3295
shale & lime	3415
lime	3460
lime & shale	3500
lime	3668
chert	3691
chert & lime	3706
chert & shale	3729
shale & lime	3750
shale & lime brkn	3770
lime	3788
Total Depth	

Tops:	
Howard	2848
Topeka	2878
Heebner	3238
Douglas	3272
Brown Lansing	3368
Lansing	3388
Base Kansas City	3628
Cherty Conglomerate	3652
Viola Chert	3666
Simpson	3713
Arbuckle	3770

PLUGGING
FILE SEC 14 T 22 R 13 W
BOOK PAGE 74 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1951
CONSERVATION DIVISION
Wichita, Kansas