

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 14 Twp. 22 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner Frank J. Black
Lease Name Fisher Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-17-61 19
Application for plugging filed 3-4-63 19
Application for plugging approved 3-5-63 19
Plugging commenced 3-5-63 19
Plugging completed 3-9-63 19
Reason for abandonment of well or producing formation Depleted.

T - 22 NORTH R - 13W



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	None
				5-1/2"	3849'	2931'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3850', sanded to 3835' and dumped 5 sacks of cement @ 3835' with dump bailer. Pulled 5 1/2" casing, bailed fluid from 60' to 200', set rock bridge to 190' and ran 20 sacks of cement @ 190'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 18 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March, 1963

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



15.185.19339.0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


Company- WILKINSON DRILLING INC.,
Farm- Fischer No. 1

SEC. 14 T. 22
NE SW NE

130

Total Depth. 3850'
Comm. 12-6-1961 Comp. 12-17-1961
Shot or Treated.
Contractor. Dunne-Gardner Drilling Co., Inc.
Issued. 8-18-1962

County Stafford
KANSAS



Elevation. 1892'

Production. 25 BOPD. NW/ARB
3770-3808

Figures Indicate Bottom of Formations.

Sand & Shale	240
Shale	255
Shale & Sand	740
Anhydrite	765
Shale	820
Shale & Shells	1650
Shale & Lime	2580
Shale & Shells	2790
Shale & Lime Strks.	2900
Lime & Shale	3370
Lime	3630
Lime & Chert	3713
Lime	3770
Lime - Arbuckle	3850
TOTAL DEPTH	3850

TOPS:	ELECTRIC LOG.
Heebner	3238
Brown Lime	3373
Lansing	3392
Conglomerate	3655
Viola	3670
Simpson	3713
Arbuckle	3765
Total Depth	3850

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1963

CONSERVATION DIVISION
Wichita, Kansas