


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 14 Twp. 22 Rge. 13 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines 100' South NE SW NE
Lease Owner Woody's Quality Oil Company
Lease Name Fischer Well No. 1
Office Address 1119 Cravens Bldg., Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-17-64 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5-17-64 19
Plugging completed 5-17-64 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240' set plug 1/4 sack hulls, 25 sacks cement through drill pipe. Filled hole to 40' with heavy mud, set plug 1/4 sack hulls filled surface pipe with cement to surface. Plugged rat hole with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas COUNTY OF Barton, ss.
L. O. Chubb contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. O. Chubb*

Box 823, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 1964

Clair E. Stimson
Clair E. Stimson Notary Public.

My commission expires 6-24-67

W E L L L O G

Date Commenced: May 6, 1964
Date Completed: May 17, 1964

Woody's Quality Oil Company
FISCHER #1
Approx. NE SW NE
Sec. 14-22S-13W
Stafford County, Kansas

0	-	45	Surface Clay & Sand
45	-	90	Sand-Gravel
90	-	247	Shale & Sand
247	-	445	Red Bed
445	-	471	Anhydrite
471	-	770	Red Bed
770	-	1081	Shale & Shells
1081	-	1542	Shale-Shells-Salt
1542	-	2037	Lime & Shale
2037	-	2505	Shale & Lime
2505	-	2794	Lime & Shale
2794	-	3236	Lime
3236	-	3240	Shale
3240	-	3273	Lime & Shale
3273	-	3370	Shale
3370	-	3389	Lime & Shale
3389	-	3645	Lime
3645	-	3668	Conglomerate
3668	-	3710	Chert
3710	-	3760	Shale & Sand
3760	-	3850	Dolomite

ELEVATION: 1891 K.B.
1883 G.L.

FORMATION DATA E Log

Heebner	3236
Douglas	3272
Brown Lime	3370
Lansing	3389
Viola	3668
Simpson	3710
Arbuckle	3760
R.T.D.	3850

SURFACE CASING: Set: 8 5/8"
at 250' with 250 sacks cement.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss.

L. O. Chubb, of lawful age, does swear that the facts and statements herein contained are true and correct to the best of his knowledge.


L. O. Chubb

Subscribed and sworn to before me this 21 day of July, 1964.

My Commission Expires:
June 24, 1967


Clair E. Stinson - Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1964

CONSERVATION DIVISION
Wichita, Kansas