

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biding Building
Wichita, Kansas

NORTH

6			

Locate well correctly on above
Section Plat

Stafford County. Sec. 20 Twp. 22 Rge. 13 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Petroleum, Inc.
Lease Name Keenan 'E' Well No. 1
Office Address 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 25, 19 53
Application for plugging filed September 25, 19 53
Application for plugging approved September 25, 19 53
Plugging commenced September 25, 19 53
Plugging completed September 25, 19 53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C.D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3,924 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 300' and set wooden plug
at 300'. Placed 1/2 sack hulls on top
of plug at 300'. Cemented and displaced
20 sacks cement through drill pipe onto
plug and hulls at 300'. Mudded up to 40'
and set second wooden plug at 40'. Placed
1/2 sack hulls on top of plug at 40'.
Filled hole to bottom of well cellar with
10 sacks cement.

10-6-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R.R. #2, Great Bend, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W.W. Fisher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.W. Fisher
305 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 19 53

Charlotte Thomson
Notary Public.

My commission expires October 13, 1954



DRILLER'S LOG KEENAN 'E' #1

Petroleum, Inc., Operator
Garvey Drilling Company, Contractor

Section 20, Twp. 22S, Rge. 13W
Location: NW SW SW
County: Stafford County, Kansas
Production: D & A
R.T.D.: 3924'

Drilling Commenced: September 13, 1953
Drilling Completed: September 25, 1953
Casing Record: 8 5/8" @ 300' w/225 sax

Figures below indicate bottom of formation:

35	Surface Soil & Clay
265	Sand & Shells
300	Shale
785	Red Shale & Shells
810	Anhydrite
1850	Shale & Shells
2180	Lime
2935	Shale & Lime
3805	Lime
3840	Lime & Chert
3924	Lime
3924	R.T.D.

TOPS:

Heebner:	3307(-1397)
Brown Lira:	3437(-1527)
Lansing:	3454(-1544)
Conglomerate:	3745(-1835)
Viola:	3775(-1865)
Arbuckle:	3874(-1964)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fisk

RECEIVED
STATE OF KANSAS
OCT 12 1953
COUNTY OF SEDGWICK

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 1st day of October, 1953.

Shirley Weidman
Notary Public

My commission expires: October 13, 1954.

PLUGGING
FILE SEC 20 T 22 R 13W
BOOK PAGE 132 LINE 18