

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-185-21,908-0000

LEASE NAME GRIMES

WELL NUMBER #1

SPOT LOCATION NE-SW-NW

SEC. 20 TWP. 22 RGE. 13 (X) OR (W)

COUNTY Stafford

DATE WELL COMPLETED 12-15-83

PLUGGING COMMENCED 12-15-83

PLUGGING COMPLETED 12-15-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Golden Belt Oil

ADDRESS 3601 - 22nd, Great Bend, Ks 67530

PHONE #(316)- 793-8975 OPERATORS LICENSE NO. 9202

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACO-1 FILED? IF NOT, IS WELL LOG ATTACHED? No Logs Ran

PRODUCING FORMATION DEPTH TO TOP BOTTOM T.D. 3885'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	312'	0

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. PTA w/175 sks 60/40 pozmix cement, 2% Gel, 3% CC, 50 sks plug @ 3880', 40 sks plug @ 780', 50 sks plug @ 350', 10 sks plug @ 40', 15 sks in Rathole, 10 sks in Mousehole.

PLUGGING COMPLETE

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287
ADDRESS 2400 Main, Great Bend, Ks 67530

STATE OF Kansas COUNTY OF Barton, SS.

Joe E. Brougher (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.


(SIGNATURE) Joe E. Brougher
(ADDRESS) Joe E. Brougher
P.O. Drawer 1367

Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 28 DAY OF Dec, 1983

Jeri Pebley
NOTARY PUBLIC

MY COMMISSION EXPIRES: 6-9-86



FORM CP-4
REVISED 06-83

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1983

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

GOLDEN BELT OIL COMPANY

GRIMES #1

NE SW NW Section 20-22-13

Stafford County, Kansas

DATE COMMENCED: 12-8-83

DATE COMPLETED: 12-14-83

SURFACE PIPE: 8 5/8" Casing @315'

- 0 - 280' Sand & Gravel
- 280 - 380' Sand & Clay
- 380 - 780' Red Bed
- 780 - 802' Anhydrate
- 802 - 1625' Shale
- 1625 - 1970' Shale w/Lime
- 1970 - 2362' Shale
- 2362 - 2745' Shale w/Lime
- 2745 - 3100' Lime & Shale
- 3100 - 3375' Lime
- 3375 - 3524' Lime
- 3524 - 3582' Lime
- 3582 - 3625' Lime
- 3625 - 3655' Lime
- 3655 - 3715' Lime
- 3715 - 3830' Lime
- 3830 - 3835' Lime
- 3835 - 3865' Lime
- 3865 - 3885' Lime
- 3885' RTD
- D/A

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Viann Brougher of lawful age, does swear and state that the facts and statements herein are true and correct to the best of her knowledge.


Viann Brougher
Viann Brougher

Subscribed and Sworn to before me this 23rd day of December, 1983.

My Commission Expires:

6-9-86

Jeri Pebley
Notary Public Jeri Pebley



RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1983

CONSERVATION DIVISION
Wichita, Kansas