

WELL PLUGGING RECORD


15-155-36217-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 32 Twp. 23S Rge. 10 (X) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW
Lease Owner Independent Lease Management
Lease Name Johnson (O.W.W.O.) Well No. 1
Office Address 800 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 16 1969
Application for plugging filed August 16 1969
Application for plugging approved 19
Plugging commenced August 16 1969
Plugging completed August 16 1969
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3819 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump heavy mud to 200'. Set plug & 1/2 sx.
hulls, cement w/30' sx. cement.
Pump heavy mud to 40'. Set plug & 1/3 sx.
hulls, cement w/15 sx. cement.
2 sx. cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kathol Petroleum, Inc.
Address 900 Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale P. Jewett (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale P. Jewett
800 Wichita Plaza, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1969

My commission expires June 9, 1973

Pearl E. Crayton
Pearl E. Crayton
Notary Public.

SEP 12 1969
COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-155-30217-0001 R

Company- MESSMAN-RINEHART OIL CO.
Farm- Jean Johnson No. 1

SEC. 32 T. 23 R. 10W
NE SE SW

Total Depth. 3816'
Comm. 2-8-62 Comp. 2-25-62
Shot or Treated.
Contractor.
Issued. 6-16-62

County Reno KANSAS



Elevation. 1788' RB

Production. Dry

CASING:

10 3/4" 205' cem w/175 sx.

Figures Indicate Bottom of Formations.

sand & clay	120
shale & red bed	205
red bed & shells	540
shale & shells	865
red bed & shells	1145
shale & shells	1425
shale, shells & lime	1495
lime & shale	2040
shale w/lime streaks	2080
lime & shale	2355
shale & lime streaks	2510
shale	2725
shale & shells	2790
lime	3280
lime & shale	3310
lime	3370
lime & chert	3415
lime	3446
lime	3614
lime & chert	3667
lime	3700
lime & chert	3720
lime & sand	3748
lime	3753
sand & shale	3795
shale & lime	3806
Arbuckle	3816 T.D.
Total Depth	

TOPS: SAMPLE

Anhydrite	461
Heebner	3100
Douglas	3166
Brown Lime	3250
Lansing	3282
Misener	3628
Viola	3638
Simpson Shale	3729
Simpson Sand	3739
Arbuckle	3800

O.W.W.O. (Independent Lease Management) 8/16/69.

Drilled Deeper: Old T.D. 3816'
lime 3816 to 3819' Total Depth

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1969
CONSERVATION DIVISION
Wichita, Kansas