


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD 15-155-20205-0000

NORTH



Locate well correctly on above
Section Plat

Remo _____ County. Sec. 32 Twp. 23S Rge. 10W (#) _____ (W)
Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Sterling Oil Corporation, Inc.
Lease Name Zenith Unit Johnson 1-9 Well No. _____
Office Address 200 West Douglas, Suite 950, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 31, 19 72
Application for plugging filed August 31, 19 72
Application for plugging approved August 31, 19 72
Plugging commenced 7:00 P. M. August 31, 19 72
Plugging completed 11:00 P. M. August 31, 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3826 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 262", Howco plug, 1/2 sack hulls, 25 sacks cement. Heavy mud to 40", Howco plug, 1/2 sack hulls, 10 sacks cement to surface, 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1972
CONSERVATION DIVISION
Wichita, Kansas

9-14-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF Kansas, COUNTY OF Rice, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God STERLING DRILLING COMPANY

(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of September, 19 72

CHARLES M. HALL--NOTARY PUBLIC
My commission expires Jan. 6, 1974

[Signature]
Charles Hall
Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas

15-155-20205-0000

WELL LOG - - - - - Zenith Unit Johnson 1-9

Located: NE-NE NW Sec. 32-23S-10W, Reno County, Kansas

OWNER: Stelbar Oil Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 24, 1972
COMPLETED: August 31, 1972

TOTAL DEPTH: 3826'

LOG

0 - 271 Sand and Shale
271 - 460 Red Bed
460 - 1050 Shale and Shells
1050 - 2667 Shale and Lime
2667 - 3635 Lime
3635 - 3672 Chert and Lime
3672 - 3676 Chert
3676 - 3760 Chert and Lime
3760 - 3766 Sand
3766 - 3823 Shale
3823 - 3826 Dolomite

CASING RECORD

Ran 6 joints 8 5/8" casing, OD 28#
used surface casing, 255' cemented
at 267' KB with 250 sacks 60/40 Pozmix 3%
HA5. Plug down 5:45 PM, 8-24-72.

Plugged.

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1972
CONSERVATION DIVISION
Wichita, Kansas