

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19867-00-00
Spot: NESESW Sec/Twnshp/Rge: 16-28S-8E
1008 feet from S Section Line, 3117 feet from E Section Line
Lease Name: FOUTS Well #: 2
County: BUTLER Total Vertical Depth: 2718 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2718		0 SX
SURF	8.675	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2017 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 02/16/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/BIT & TUBING, CIRCULATED HOLE CLEAN @ 2680. SANDED WELL BACK @ 2487', DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 250'-251'. (4 HOLES). RIH W/TUBING @ 270', COPELAND ACID SERVICE MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL W/ 250# HULLS. NO CIRCULATION. RIH W/1" TUBING ON BACKSIDE @ 230'. COPELAND ACID MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1", TOPPED WELL BACK TO SURFACE W/35 SXS 60/40 POZMIX 4% GEL. CEMENT CIRCULATED. CEMENT TICKET #44889. 190 SXS TOTAL.

Perfs:

Top	Bot	Thru	Comments
2690	2692	CSG	

Remarks: COMPLIANCE/DENIED TA

Plugged through: TBG

INVOICED
MAR - 6 2017

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

✓