

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24236-00-00
Spot: E2NWSWNW Sec/Twnshp/Rge: 25-14S-16W
3630 feet from S Section Line, 4875 feet from E Section Line
Lease Name: BAUMRUCKER B Well #: 3
County: ELLIS Total Vertical Depth: 3340 feet

Operator License No.: 32016
Op Name: PIONEER RESOURCES INC.
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3343		125 SX
SURF	8.625	210		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2017 9:30 AM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: JOEL STUHL Company: PRAIRIE HAWK WELL SERVICE L Phone: (785) 650-3118

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/300 # hulls.
DV Tool at 918' w/300 sx cement.
Packer stuck in hole at 3237'. Some rods and tubing.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2017 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Prairie Hawk ran in hole with tubing to 3100'. Quality rigged to tubing and pumped 110 sx cement w/200 # hulls mixed in. Pulled tubing to 1450'. Rigged to tubing and pumped 110 sx cement w/100 # hulls mixed in to circulate cement into steel pit. Pulled tubing. Rigged to 4 1/2" casing and pumped 15 sx cement to fill 4 1/2" casing. Rigged to 8 5/8" surface casing and pumped 4 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 38.80820 -099.05747

Perfs:

Top	Bot	Thru	Comments
3310	3312		


KCC WICHITA
FEB 24 2017
RECEIVED
INVOICED
MAR - 6 2017

Remarks: QUALITY OILWELL CEMENTING TICKET # 004

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

C M

FEB 16 2017