

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-20631-00-00  
Spot: S2SW Sec/Twnshp/Rge: 28-33S-6W  
1330 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: WELCH Well #: 1  
County: HARPER Total Vertical Depth: 4955 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4931	1070	175 SX
SURF	8.625	249		200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2016 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 635-5287

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/01/2016 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4398'. THE CASING WAS CIRCULATED WITH MUD & 10 SKS CEMENT WAS SPOTTED ON BP. CUT & PULLED 1070' OF CASING. RAN TUBING TO 1000' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 700' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 300' & CIRCULATE CEMENT TO SURFACE WITH 85 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4448	4460		Mississippian

Remarks: ORR ENTERPRISES, CLASS C CEMENT

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
MAR - 6 2017