

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20600-00-01
Spot: W2E2SWNW Sec/Twnshp/Rge: 7-17S-8W
3300 feet from S Section Line, 4589 feet from E Section Line
Lease Name: RATHBUN A JACK Well #: 1
County: ELLSWORTH Total Vertical Depth: 2461 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2000		
CIBP		2175		
PROD	4.5	2460	1165	120 SX
SURF	8.625	242		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/24/2017 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: TANNER NELSON Company: TREK AEC LLC Phone: (620) 755-2571

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/24/2017 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. SET CIBP AT 2000' AND CAPPED WITH 2 SX'S CEMENT. SHOOT CASING OFF AT 1165' AND PULL OUT OF HOLE. RUN TUBING TO 1100' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. LET SET AWHILE, TAGGED CEMENT AT 1010'. PUMPED 35 SX'S AT 800', PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF. USED 155 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
2034	2158	CSG	

Remarks: TA - N.O.V. LETTER SENT ON THIS WELL. CP-111 WAS NEVER SUBMITTED & FILED. PERF TECH #13481.
GLOBAL CEMENT TICKET #2844.

Plugged through: TBG

INVOICED
MAR - 6 2017

District: 02

Signed Virgil Clothier
(TECHNICIAN)