

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20565-00-00
Spot: SWSE Sec/Twnshp/Rge: 26-22S-19W
660 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: RUGGE Well Number: 1
County: PAWNEE Total Vertical Depth: 4407 feet

Operator License No.: 3972
Op Name: GLENWOOD RESOURCES, INC.
Address: 3440 YOUNGFIELD ST. #278
WHEAT RIDGE, CO 80033

Production Casing Size: 4.5 feet: 4405
Surface Casing Size: 8.625 feet: 326

14323

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2003 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BRAD SEIB Company: GLENWOOD RESOURCES Phone: (785) 798-7100

Proposed Plugging Method: PUMP 200# HULLS & 40 SX CMT. GEL SPACER TO 1000'. PUMP 1000' TO SURFACE WITH CMT. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/23/2003 10:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 4345'. PERFS AT 3974-78' & 4359-63'. DV TOOL @ 896' WITH 300 SX CMT. PUMP DOWN 4 1/2" CASING WITH 200# HULLS - 40 SX CMT - 15 SX GEL - 55 SX CMT. MAXIMUM PRESSURE 1400 PSIG. SHUT IN PRESSURE 600 PSIG. PRESSURED 8 5/8" X 4 1/2" ANNULUS WITH 15 SX CMT. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 500 PSIG.

RECEIVED
OCT 28 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 10-28-03
INV. NO. 2004060689

Form CS-213