

To: 1 120608  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-13  
API NUMBER 15- 185-22,775-0000 770

SW NW SW, SEC. 36, T 22 S, R 12 W EX

1650 feet from S section line

4950 feet from E section line

Lease Name Dennis Well # 1  
Stafford  
County 119.43

Well Total Depth 3675 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 249

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Operator: L.D. Drilling, Inc.

Name & Address RR 1, Box 183 B

Great Bend, KS 67530

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 4 p.m. Day: 13 Month: 8 Year: 19 91

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 563-83'  
Elevation 1824'

1st plug at 600' with 50 sx cement,

2nd plug at 270' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-15-91  
AUG 15 1991  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:30 p.m. Day: 13 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 270' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

**INVOICED** (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 8-28-91

Signed Duane Rankin  
(TECHNICIAN)

INV. NO. 32872

EFFECTIVE DATE: 5-12-91

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas 15. 185-22,775-0000

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL  
Must be approved by the K.S. E. five (5) days prior to commencing well

Expected Spud Date May 15 1991  
month day year

SW NW SW Sec 36 Twp 22 S, Rg 12 East West

OPERATOR: License # 6039  
Name: L. D. DRILLING, INC.  
Address: R. R. 1 BOX 183 B  
City/State/Zip: GREAT BEND, KS. 67530  
Contact Person: L. D. Davis  
Phone: (316) 793-3051

1650 feet from South line of Section  
4950 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6039  
Name: L. D. DRILLING, INC.

County: STAFFORD  
Lease Name: DENNIS Well #: 1  
Field Name: WC (Pleasant Grove South Rev)

Well Drilled For: Well Class: Type Equipment:  
 Oil  Inj  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OWO  Disposal  Wildcat  STATE INFORMATION COMMISSION  
 Seismic;  # of Holes

Is this a Prorated Field?  yes  no  
Target formation(s): arbuckle  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: est. 1827 feet MSL  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no  
Depth to bottom of fresh water: 110'  
Depth to bottom of usable water: 200'  
Surface Pipe by Alternate:  1  2  
Length of Surface Pipe Planned to be set: 220'  
Length of Conductor pipe required: none  
Projected Total Depth: 3700'  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  well  farm pond  other

If OWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

AUG 15 1991

DWR Permit #: applied for  
Will Cores Be Taken?:  yes  no  
If yes, proposed zone: \_\_\_\_\_  
220' Alt. I Req.

Exp. 11/7/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Greg David Gay INIT. R.L.  
SPUD DATE 8-8-91  
LENGTH SURFACE PLANNED 220'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbbs. when done bbbs.  
RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 2 7/8 @ 249 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- 563 B- 83 ELEVATION 1824  
TD 3675 FORMATION ALB. 3653  
RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ 40 SX  
\_\_\_\_\_ Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
/ \_\_\_\_\_ Anhydrite Base @ 600 Ft. W/ 50 SX  
\_\_\_\_\_ 1/2 Base Anhy. @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
\_\_\_\_\_ 1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
\_\_\_\_\_ Bottom Surface @ 270 Ft. W/ 50 SX  
\_\_\_\_\_ 40' Plug @ \_\_\_\_\_ Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX  
WATER WELL Farm \_\_\_\_\_ Well \_\_\_\_\_ Pond \_\_\_\_\_  
TECHNICIAN DK DATE 8-12-91 Hauling \_\_\_\_\_  
TYPE OF CEMENT \_\_\_\_\_ 60-40-670  
STARTING TIME 4:00 (AM/PM) DATE 8-15-91  
COMPLETION TIME 5:30 (AM/PM) DATE 8-13-91  
CEMENT COMPANY Arco  
Arco