

To: 1052191
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

11-10

API NUMBER 15-185-01,058-0001 ³⁰¹⁹⁸

SE SE NW, SEC. 33, T 22 S, R 12 W/X
2310 feet from NX section line
2310 feet from WX section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5228
Operator: Parrish Corporation
Name & Address 110 S. Main, Ste. 510
Wichita, KS 67202-3745

Edna
Lease Name Spangenberg Well # 1 OWWO
County Stafford 122,30
Well Total Depth 3763 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 10 Month: 11 Year: 19 97

Plugging proposal received from James Ray

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Perfs: 5 1/2" at 3760', PBTD 3716', Perfs at 3640-3438'

- 1st plug sand back to 3388' and dump 5 sx cement on top of sand through bailer,
- 2nd plug at 650' with 50 sx cement,
- 3rd plug at 270' with 50 sx cement,
- 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 10 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3388' and dumped 5 sx cement on top of sand through bailer,

- Spotted plugs through tubing: 11-18-97
- 2nd plug at 650' with 8 sx gel, 50 sx cement, and 2 sx gel,
 - 3rd plug at 270' with 50 sx cement,
 - 4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1635' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
NOV 24 1997
DATE NOV 24 1997
INV. NO. 49573

Signed Richard W. Lacy
(TECHNICIAN)