

1080079

15-185-20625-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - Not Available

SW 1/4, Sec. 33, T 22 S, R 12 W/E

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Spangberg Well # 1

Operator: Brougner Oil, Inc.
Name & P. O. Drawer 1367
Address Great Bend, KS 67530

County Stafford

Well Total Depth 3717 feet 120.80

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 25 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Neal Peddicorn

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2 set at 3717 PBTB 3600. Perfs 3504 to 06 3335 to 40. Sand back to 3300'. Pumped 5 sx cement through bailer. Recovered 2700'. Squeezed well with 3 sx hulls, 20 sx gel, 50 sx cement, 5 sx gel, 15 sx hulls and released 8 5/8 plug followed by 100 sx cement.

Signed J. B. Truf (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00 pm Day: 25 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3717 PBTB 3600. Perfs 3504 to 06 3335 to 40.

Sand back to 3300'. Pumped 5 sx cement through bailer. Recovered 2700'. Squeezed well with 3 sx hulls, 20 sx gel, 50 sx cement, 5 sx gel, 15 sx hulls and released 8 5/8 plug followed by 100 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc. by Halliburton

Max pressure 650# Shut in pressure 375#

RECEIVED STATE CORPORATION COMMISSION

FEB 02 1984

CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed J. B. Truf (TECHNICIAN)

FORM CP-2/3 Rev. 9-82

INVOICED

DATE

2-3-84

NO. 0037