

To: 121075 10-17
STATE CORPORATION COMMISSION
Wichita State Office Bldg. **PLUGGING SECTION**
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 10/9/30 15-185-02001-0000
SE SE SE, SEC. 36, T 22 S, R 12 W/E
220 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613
Operator: Hallwood Petroleum, Inc.
Name & Address: 4582 S. Ulster St. Pkwy, Ste. 1700
Denver, CO 80237

Lease Name T. Richardson Well # 1
County Stafford
Well Total Depth 3601 117.03 feet
Conductor Pipe: Size feet
Surface Casing: Size 20 feet 151

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 17 Month: 10 Year: 19 95

Plugging proposal received from Richard McIntyre
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 20" casing set @ 151'-couldn't find top, 15 1/2" casing set at 548', all pulled,
13 3/8" casing set at 980', 10 3/4" casing set at 2836', 8 5/8" casing set at 3253'-pulled
750', 6 5/8" casing set at 3478'-pulled 700', Perfs at 3311-3440'

1st plug sand back 6 5/8" casing to 3250' and dump 7 sx cement on top of sand through bailer,
2nd plug shoot 10 3/4" casing at 250', run tubing to 650' and circulate cement, 3rd plug
pull tubing and squeeze casing Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 5 p.m. Day: 17 Month: 10 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 6 5/8" casing back to 3250' and dumped 7sx cement
on top of sand through bailer,

2nd plug shot 10 3/4" at 250', ran tubing to 650' and pumped 260 sx cement, cement circulated,
3rd plug pulled all tubing and squeezed 10 3/4" X 13 3/8" with 150 sx cement
Shut in with 150 psi.

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1995
10-23-95
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If you wish to observe this plugging.)

DATE 10-27-95
INV. NO. 43868

Signed Duane Rankin
(TECHNICIAN)