

To: 1 120035
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-16-87 15-185-21863-0000
API NUMBER 15-Drill completion 10/26/83

NE SE NW, SEC. 27, T 22 S, R 11 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6166

Lease Name Curtis Well # 2

Operator: Bill Chew, Inc.
Name & Address: P.O. Box 90
Lyons, KS 67554

County Stafford 118.95
Well Total Depth 3660 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 16 Month: 10 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3659' Top perf at 3290' Elevation 1803' GL

1st plug sand back to 3240' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 16 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3240' and dumped 5 sx cement on top of
sand with dump bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 15 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

OCT 21 1987 10-21-87

Pumping pressure 4-500 psi and shut in 200 psi.

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2345' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Date / Amount observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 10-22-87

INV. NO. 18611