

To: 040810 12-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
203 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-D-23,136 15-185-20846-00-01
N/2 SW NE, SEC. 27, T 22 S, R 11 W/EX
3630 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6153
Operator: Chew Oil & Gas Company
Name & Address P.O. Box 90
Lyons, KS 67554-0090

Lease Name Morris Well # 2
County Stafford 119.99
Well Total Depth 3692 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 3 Month: 12 Year: 19 93

Plugging proposal received from Joe Linke
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3692' w/150 sx cement, CIBP at 3620', Perfs at 3260-64, 3284-88, 3314-18'
1st plug sand back to 3200' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 2:45 p.m. Day: 3 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3200' and dumped 5 sx cement on top of sand
bridge through bailer.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1934' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / ~~did not~~) observe this plugging.
DATE DEC 14 1993
INV. NO. 39506

RECEIVED
STATE CORPORATION COMMISSION
DEC 09 1993
Signed Stephenson
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-27