

To: 1 120686
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,390-0000 ²⁻²⁶ ¹⁵⁴
SW SW NW, SEC. 21, T. 22 S, R. 11 W/E ^R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

2970 feet from S section line

4950 feet from E section line

Operator: Lebsack Oil Production, Inc.

Lease Name NW Sleeper Well # 1

Name & Address P.O. Box 489

County Stafford

Hays, KS 67601

Well Total Depth 3660 ^{118.95} feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

RECEIVED
STATE CORPORATION COMMISSION

Company to plug at: Hour: 8 a.m. Day: 26 Month: 2 Year: 19 92

FEB 28 1992

Plugging proposal received from Monte

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

CONSERVATION DIVISION
Wichita, Kansas

were: 5 1/2" at 3658' w/200 sx cement. Open hole

1st plug sand back to 3220' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:30 a.m. Day: 26 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3600' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2130' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
XXXXXX observe this plugging.

DATE 3-5-92

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 34674