

JK
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leo G. Wetherill Jr.

Complete Address: 2208 Power & Light Bldg., Kansas City, Missouri

Lease Name Spangenberg Well No. # 1

Location SE SE NW Sec. 33 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Duke Drilling Company

Address: Box 823, Great Bend, Kansas License No.

Operation Completed: Hour 12:45AM Day 22nd Month April Year 1965

The Above well was plugged as follows:

238' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid
level in the hole was at 80'. 1st cementing plug and 1 sack of hulls
was pushed in fluid to 215', and cemented with 25 sacks, through the
drill pipe. Fluid in the hole was now at 38', 2nd cementing plug was
bridged solid with dry cement and hulls on fluid at 38', and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cement-
ed with 2 sacks.

RECEIVED

I hereby certify that the above well was plugged as herein stated.

INVOICED APR 23 1965

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/26/65
CONSERVATION DIVISION
Wichita, Kansas
INV. NO. 1051-11