

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. _____

LOCATION NE NE NWSEC. 33 TWP. 22 RGE. 18WDry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease SpangenbergOperator Sirringhaus & Berthel Address 215 Peter Bldg - Wichita - KansasField _____ County StaffordTotal Depth 3732 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 243 ft - Circulated with cement.
3 1/2" casing set at 3705 ft - Plugged back from bottom
with chat to 3700 ft - Pumped 5 sacks of cement
at 3700 ft - Ripped 4 1/2" & pulled the 3 1/2" casing
filled with mud to 243 ft - Set Rock Bridge &
15 sacks of cement at 243 ft - Mud to 30 ft - Bridge
& 10 sacks of cement at the surface -

MAR 10 1950

3-10-50

STATE CORPORATION
COMMISSIONC. M. Strong
District Conservation AgentDate 3-7-50

PLUGGING
 FILE SEC 33 T 22 R 18W
 BOOK PAGE 141 LINE 31