

KANSAS

FORM CP-3

Rev. 10-8-81

STATE CORPORATION COMMISSION

RECEIVED

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

DEC 4 1981

API Number 15-155-

CONSERVATION DIVISION

Wichita Kansas

12-7-81

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Zenith Drilling Corporation

Complete Address 505 Fourth Financial Center, Wichita, Kansas 67202

Lease Name Culver "B" Well No. 2

Location SE NW SW Sec. 6 Twp. 22 Rge. 9 (~~East~~) (West)

County Reno Total Depth 3645'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling and Halliburton Co.

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour: 11:45 AM Day: 4 Month: December Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: 8 5/8" - 242' - 200 sacks 4 1/2" - 3644' - 125 sacks Per-F. 3600-05' PBTD 3620'

Hole Filled with sand to 3550' and cemented with 4 sacks cement.

Hole squeezed with 4 sacks hulls, 25 sacks gel-mud, and 100

sacks 50-50 Pozmix w/2% gel pumped into 8 5/8" surface casing.

Pressure ranged from 3000 PSI to close in pressure of 250 PSI.

3120' of 4 1/2" casing recovered

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: Alvin J. Lomas
Conservation Division Agent

DATE 1-21-82

CHK. NO. 9109-W-

118-416