

46
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

OCT 10 1963
10-10-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lario Oil & Gas Company

Complete Address: 301 So. Market, Wichita, Kansas

Lease Name Haltom Well No. 2

Location C NW SE Sec. 6 Twp. 22 Rge. 9 (E) (W) X

County Reno Total Depth 3648'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith Pipe Pulling Co.

Address: 204 E. 6th, Ellinwood, Kansas License No. 396

Operation Completed: Hour 3:30PM Day 5 Month October Year 1963

The Above well was plugged as follows:

4 1/2" plug pushed to 3600'. Hole filled with sand to 3590' and cemented
with 3 sacks. Hole filled with mud to 220'. Rock bridge set from 220'
to 210' and cemented with 20 sacks. Hole filled with mud to 40'. Rock
bridge set from 40' to 30' and hole cemented to base of cellar with
10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *J. P. Roberts*
Well Plugging Supervisor

DATE 10/10/63

INV. NO. 17845-W