

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
AUG 9 1967
8-9-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 11, 1967.

Operator's Full Name Strata Drilling Company

Complete Address Box 355, Great Bend, Kansas 67530

Lease Name Curtis "AA" Well No. # 1

Location SE NE NW Sec. 27 Twp. 22 Rge. 11 (E) (W)W

County Stafford Total Depth 3696'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:30 A.M. Day 7th Month August Year 1967

The above well was plugged as follows:

198' of 8 5/8" surface pipe, cement circulated. 3695' of 4 1/2" long string,
cemented with 100 sacks. Top perforation 3638'. Bottom of the hole was sanded
to 3600', and cemented with 4 sacks, with cement from 3600' to 3550'. 2100' of
4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid
to 210', bridge plug and rock bridge from 210' to 200'. 6 sacks of cement was
mixed in a barrel, and put on plug at 200', through the dump bailer, and let
set over-night. Next day hole was bailed dry, and 19 sacks of cement was added
to the plug, with cement from 200' to 125'. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30'
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 8/9/67
INV. NO. 6101-4