

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-185-22,605-0000 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Hellar Drilling Co., Inc. OPERATOR'S LICENSE NO. 5015

ADDRESS 125 N. Market, Suite 1422, Wichita, KS 67202 PHONE # (316) 267-2845

LEASE (FARM) Sleeper "A" WELL NO. 1 WELL LOCATION SW SE NE COUNTY Stafford

SEC. 22 TWP. 22S RGE. 11 (~~EXXX~~W) TOTAL DEPTH 3696' PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 258' CEMENTED WITH 160 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 800'-50 sx. 2nd  
plug at 510'-50 sx. 3rd plug at 290'-40 sx. 4th plug at 40' SB-10 sx. Rathole-15 sx. All  
cement 60/40 pozmix, 6% gel

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No  
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 6:30 p.m. on 9-23-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: \_\_\_\_\_

William Craig, Sr. PHONE # (913) 674-2876 10-19-89

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841 Wichita, Kansas

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton  
(Operator or Agent)

DATE: October 17, 1989