

HALTOM NO. 1 WELL

NE¹/₄NE¹/₄SE¹/₄ Sec. 6-22s-9w,
Reno County, Kansas

OWNERS: N. Appleman Company et al


CONTRACTOR: Hollow Drilling Company, Inc.
Inman, KansasPipe RecordDate Commenced: July 6, 1942
Date Completed: July 20, 1942Ran 12 jts. SH 8 5/8 Surface Casing
258' 1", cemented with 75sx Regular
and 25 sx Regular Caci at 253',
Cement circulated.

Tools: Rotary Drilling Tools.

Log.

0	8 Cellar
8	70 Clay
70	105 Sand and Gravel
105	253 Red Rock
253	350 Red Rock
350	370 Anhydrite Lime
370	900 Shale and Shells
900	1225 Salt and Lime Shells
1225	1425 Lime and Shale
1425	1545 Lime
1545	1690 Shale and Lime
1690	1925 Lime
1925	2065 Lime and Shale
2065	2350 Lime and Shale
2350	2440 Lime
2440	2515 Shale
2515	2680 Lime
2680	2880 Lime
2880	2930 Lime and Shale
2930	2985 Lime
2985	3130 Shale and Lime Shells
3130	3378 Lime
3378	3439 Lime and Shale
3439	3469 Shale and Red Rock
3469	3482 Lime and Chert
3482	3523 Shale and Lime
3523	3548 Lime
3548	3553 Coring Viola Lime 4 ft. recovery.
3553	3618 Lime
3618	3662 Shale & Sand
3662	3670 Shale
3670	3674 Arbuckle Lime
3674	3679 Cored-Recovered 4'
3679	3720 Lime
3720	T. D. Equals 3718' Derrick Floor. Dry and Abandoned.

<u>Tops</u>	<u>Depth</u>
Anhydrite	Plus 1396 DF
Kansas City	Minus 1435 DF
Conglomerate	Minus 1707 DF
Kinderhook	Minus 1754 DF
Viola	Minus 1782 DF
Simpson	Minus 1863 DF
Arbuckle	Minus 1922 DF
T.D.	Minus 1972 DF

Coring RecordCored 3543 to 48 recovered 4' Viola
3674 to 79 recovered 4' Arb.RemarksAll measurements subtract 2' for
Derrick Floor measurement.I, W. B. Hollow, hereby certify that the
above and foregoing is a true and accurate
copy of the log of the Haltom #1 well located
in the SE¹/₄ Section 6-22s-9w, Reno County,
Kansas.