

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,054-0000

LEASE NAME Key

WELL NUMBER B-3

SPOT LOCATION NE NW NW

SEC. 6 TWP. 22 RGE. 9 CORNER (W)

COUNTY Reno

Date Well Completed 6-2-85

9:30 PM

Plugging Commenced 6-2-85

10:45 PM

Plugging Completed 6-2-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Zenith Drilling Corporation

505 Fourth Financial Center

ADDRESS Wichita, Kansas 67202

PHONE # (316) 265-6697 OPERATORS LICENSE NO. 5141

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 2

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3583'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from ___ feet to ___ feet each set.

Filled hole with heavy mud, 40 sacks at 3500'; 35 sacks at 320'; 25 sacks at 60', 10 sacks in rathole. Used 50/50 Pozmix, 2% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss. STATE CORPORATION COMMISSION

F. A. Wuellner

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner

F. A. Wuellner, Secretary

(Address) P. O. Box 129

Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1985



Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-89

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - KEY B-3

Located: NE NW NW, Section 6-22S-9W, Reno County, Kansas

OWNER: Zenith Drilling Corporation
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 28, 1985
 COMPLETED: June 2, 1985

TOTAL DEPTH: 3583'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 110	Clay and Sand	Ran 6 joints 8 5/8" casing. 255.18' pipe set at 267' K.B. Cemented with 210 sacks Common, 2% gel and 3% cc. Plug down at 2:30 PM, 5-28-85, by Howco.
110 - 270	Red Bed	
270 - 895	Shale	
895 - 913	Anhydrite	
913 - 3533	Lime and Shale	
3533 - 3550	Lime	Plugged.
3550 - 3583	Lime and Shale	

RECEIVED
 STATE CORPORATION COMMISSION

JUN 07 1985

Deviation Surveys: 1° at 1630'
 1° at 3583'

CONSERVATION DIVISION
 Wichita, Kansas